



Oregon Department of Transportation

Highway Project Information

Area 3 Project Office: Salem (503) 986-2900

State Highway Development and Construction in Marion, Polk and Yamhill Counties

OR22: Sourgrass Creek (Indian Bridge)

Updated: 11/30/06 ML

Project location

- Oregon Route 22, Three Rivers Highway, Yamhill County (MP 12.45-12.58)
- Between Grand Ronde and Hebo (Dolph Jct.)

Project purpose and need

- The existing 9 ft diameter metal culvert is deteriorating from rust giving way to holes in the bottom of the culvert. Creek water is flowing under the culvert which causes serious undermining and embankment washout which compromises the 20-30 ft roadway fill above the culvert. A new bridge will be constructed over Sourgrass Creek to replace the failing culvert and improve fish passage.

Construction overview

- Tree and brush removal will occur prior to March 1st
- Construct ½ of the new bridge at a time with a continuous one lane closure, 24 hour flagging
- Up to four full weekend closures will be allowed to place the bridge beams and switch traffic
- Signed detours will be in place and enforced during the weekend closures
- Existing culvert and fill will be removed after the bridge is in place
- Slide stabilization and stream channelization will also be done

Construction Cost Estimate

- \$2,113,120
- Federal funds

Key project milestones

- Bid Let Date — November 16, 2006
- Construction – July - December 2007

For more information contact:

- McGregor Lynde, Project Leader, (503) 986-2666, e-mail: mcgregor.lynde@odot.state.or.us
- Jyll Smith, Community Affairs Representative, (503) 986-5845, e-mail: jyll.e.smith@odot.state.or.us