

SP320 (03-3106-26-08)

SECTION 00320 - CLEARING AND GRUBBING

(Follow all instructions. If there are no instructions above a subsection, paragraph, sentence, or bullet, then include them in the project but make necessary modifications to only include project specific specifications. Delete specifications that do not apply to the project.)

~~*(Use the following paragraph when subsections 00320.40(b) and .90 are NOT included in the project.)*~~

~~Comply with Section 00320 of the Standard Specifications.~~

~~*(Use the following lead-in paragraph when subsections 00320.40(b) and .90 are included in the project.)*~~

Comply with Section 00320 of the Standard Specifications modified as follows:

(Use the following subsection .40(b) when trees are to be saved.)

00320.40(b) Preserving and Trimming Vegetation - Add the following to the end of this subsection:

(4) Trees To Be Saved - The Engineer will identify and mark trees to be saved. Provide and place orange plastic mesh fencing, from the QPL, around critical root zones of marked trees or tree groups as directed. Do not begin construction activity or move equipment into existing tree areas until the plastic mesh fencing is in place.

Do not work within the critical root zone of marked trees unless written approval is obtained from the Engineer. Be responsible for all damage to or for removal of marked trees. Tree damage will be determined by a certified arborist selected by the Engineer.

00320.42 Ownership and Disposal of Matter - Replace this subsection with the following subsection:

00320.42 Disposal of Matter - Dispose of all matter and debris according to 00290.20.

(Use the following subsection .9190 when trees are to be saved.)

00320.90 Payment - Add the following after the first paragraph of this subsection:

No separate or additional payment will be made for plastic mesh fencing.