

SECTION 00759 - MISCELLANEOUS PORTLAND CEMENT CONCRETE STRUCTURES

(Follow all instructions. If there are no instructions above a subsection, paragraph, sentence, or bullet, then include them in the project but make necessary modifications to only include project specific specifications. Delete specifications that do not apply to the project.)

(Use the following lead-in paragraph when subsections 00759.00 and .90 are NOT included in the project.)

Comply with Section 00759 of the Standard Specifications.

(Use the following lead-in paragraph when subsections 00759.00 and .90 are included in the project.)

Comply with Section 00759 of the Standard Specifications modified as follows:

(Use the following subsection .00 on projects that have only retrofitting existing sidewalks or existing sidewalk ramps with new sidewalk ramps. Do not use on projects that have other new sidewalk construction.)

00759.00 Scope - Add the following:

This work consists of removing existing concrete walks and curbs, and constructing new portland cement concrete sidewalk ramps with curbs.

(Use the following subsection .90 when adding pay items. Delete items that do not apply. Include pay item (j) on projects that have only retrofitting existing sidewalks or existing sidewalk ramps with new sidewalk ramps. Do not use pay item (j) on projects that have any other new sidewalk construction.)

00759.90 Payment - Add the following pay items:

Pay Item	Unit of Measurement
----------	---------------------

(k) Concrete Driveway Connections.....	Square Foot
(j) Concrete Sidewalk Ramps.....	Each

(Use the following paragraphs when pay item (j) is included in the project.)

Delete the paragraph that reads "Items (e) and (f) include sidewalk ramps."

Add the following paragraph:

Item (j) includes saw cutting and removing existing concrete walks, curbs, or ramps, and replacing them with new sidewalk ramps and curbs.