



BLIND RANDOM DENSITY

SPECIAL PROVISIONS REFERENCE

00745.49(b-2) Random Testing - Replace the paragraph of this subsection that begins with “Determine the density of each subplot by averaging...” with the following paragraphs:


Correspond lots and **compaction sublots** with those defined in 00745.02. **Provide one density test location for each compaction subplot.** Notify the Engineer when rolling operations are completed in a compaction subplot and it is ready for test location identification. The Engineer will use stratified random numbers to locate the QC tests according to ODOT TM 400 Annex. ODOT TM 400 Annex is available from the Engineer. The Engineer will mark where the QC tests are to be performed.

Allow 30 minutes for the Engineer to locate the final test locations after completion of finish rolling and any additional time required for testing, prior to opening the travel lane to traffic. Have the CDT locate and document the test locations not identified within this time frame.

Points of Interest for Blind Random Density

- Still some concerns regarding time management – balancing Blind Random and other inspection responsibilities
- Reconcile yields daily with number of tests taken to ensure that any missing tests are recovered ASAP
- Use the ticket taker to record the station at each random tonnage to be located later by an inspector for the CDT
- Tablets are a good field tool to run the calculations and help keep track of the ongoing changes

BLIND RANDOM DENSITY WORKBOOK



MATERIAL DELIVERY & YIELD CHECK SHEET

Page of

PROJECT CONTRACT

DATE SOURCE

BID ITEM MATERIAL

LOAD #	TICKET #	QUANTITY DELIVERED	LOCATION PLACED	TIME DELIVERED	CUMULATIVE DELIVERED	REMARKS	(Width)
1					0.00		
2					0.00		
3					0.00		
4					0.00		
5					0.00		
6					0.00		
7					0.00		
8					0.00		
9					0.00		
10					0.00		
(A) Total							

(B) THEORETICAL YIELD CALC: $(\text{Width} \times \text{Length} \times (\text{Depth}/12) \times (\text{MAMD} \times \% \text{Comp}/100) / 2000) = \text{TONS}$

WIDTH (Ft)	LENGTH (Ft)	DEPTH (In)	MAMD	% COMPACTION	THEORETICAL TONS
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

(C) COMPARISON CALC: $(A/B) \times 100$ (D) % TOLERANCE CALC: $(100-C)$ (expected tolerance to be within +/- 10.0%)


Ten Load Yield (A)	<input type="text"/>	* Initial here if yield calculations are not applicable due to irregular areas or lack of consistent placement
heoretical Tons (B)	<input type="text"/>	
Comparison (C)	<input type="text"/>	
% Tolerance (D)	<input type="text"/>	

When +/- 10.0% tolerance is exceeded, verify Depth, Width, and Length, then MAMD and Compaction. Notify Contractor of unsatisfactory yield that needs adjustment. Continue checking yields.

DAILY THEORETICAL YIELD CALCULATION (expected tolerance to be within +/- 10.0%)

(Avg Width x Overall Length x (Avg Depth/12) x (MAMD * Avg %Comp./100) / 2000) = TONS

WIDTH (Ft)	LENGTH (Ft)	DEPTH (In)	MAMD	% COMPACTION	THEORETICAL TONS	TOLERANCE
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>



MATERIAL DELIVERY & YIELD CHECK SHEET

Page of

PROJECT CONTRACT

DATE SOURCE

BID ITEM MATERIAL

LOAD #	TICKET #	QUANTITY DELIVERED	LOCATION PLACED	TIME DELIVERED	CUMULATIVE DELIVERED	REMARKS	(Width)
11					0.00		
12					0.00		
13					0.00		
14					0.00		
15					0.00		
16					0.00		
17					0.00		
18					0.00		
19					0.00		
20					0.00		
Subtotal					0.00		
Running Total					0.00		

Yield	Width	Length	Depth	MAMD	% Comp	Theoretical Tons	Tolerance
10-Load	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Running	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

LOAD #	TICKET #	QUANTITY DELIVERED	LOCATION PLACED	TIME DELIVERED	CUMULATIVE DELIVERED	REMARKS	(Width)
21					0.00		
22					0.00		
23					0.00		
24					0.00		
25					0.00		
26					0.00		
27					0.00		
28					0.00		
29					0.00		
30					0.00		
Subtotal					0.00		
Running Total					0.00		

Yield Check Sheet Ticket Taker Tab Inspector Tab +

The Yield Tab has the updates from the 2021 Forum, including the 10-load and running yield options with each 10 loads. We also included the daily yield check and columns for cumulative tons delivered and width.

RECOMMENDED BLIND RANDOM WORKBOOK INSPECTOR TAB

Blind Random Numbers for ACP Density												
Project Name:										Contract Number:		
Project Manager:					Description:			Mix Design Number:		Bid Item No.:	Lot:	
Lot -		Three Random Digits	Date	Random Tonnage	Asphalt Tonnage to Date	Adjusted Daily Random Tonnage	Test Station	Two Random Digits (D)	Width of Panel Feet (E)	Distance From Right Edge ((E-2)*D)+1	Sublot Size	
Sublot					Cumulative Tonnage from Previous Shift		Ticket Taker or Calculated				Tons	
L	S	#										
		1	0.638	05/10/22	128		100+64	0.19	14.0	3.3	0	
		2	0.705		341			0.76			200	
		3	0.260		452			0.59			400	
		4	0.403		681			0.49			600	
		5	0.804		961			0.46			800	
		1	0.666		1133			0.63			1000	
		2	0.319		1264			0.90			1200	
		3	0.211	05/11/22	1442	1402.23		0.97			1400	
		4	0.489		1698			0.20			1600	
		5	0.601		1920			0.05			1800	
		1	0.057		2011			0.08			2000	
		2	0.855		2371			0.93			2200	
		3	0.873		2575			0.88			2400	
		4	0.827		2765			0.49			2600	
		5	0.253		2851	2819.46		0.63			2800	
		1	0.635		3127			0.92			3000	
		2	0.292		3258			0.94			3200	
		3	0.653		3531			0.52			3400	
		4	0.476		3695			0.22			3600	
		5	0.068		3814			0.56			3800	

The Inspector Tab is updated daily and resets the random tonnage to account for the delivery tickets restarting at zero each shift. This makes it easier for the Inspector to keep track of the test tonnages without additional calculations. This tab should be updated daily by the Inspector or QCCS, who will then transfer the appropriate information to the Ticket Taker Tab.

1000+59
⊕ 2.6
(10-3)

❖ Site Locations must be marked after finish rolling, ASAP, to prevent Construction delays.



222
14+66
C-81-1

